



**NOTES:**

1. WATER SHALL ONLY BE DRAWN INTO THE CONTRACTOR'S MAIN THROUGH A DISTRICT-APPROVED RPA TYPE BACKFLOW PREVENTION ASSEMBLY. PRIOR TO CONNECTION TO THE DISTRICT WATER MAIN, THE ASSEMBLY MUST BE TESTED BY A SACRAMENTO COUNTY CERTIFIED BACKFLOW PREVENTION ASSEMBLY TESTER AND WRITTEN TEST RESULTS PROVIDED TO THE DISTRICT.
2. FINAL COMPONENTS NECESSARY FOR THE TIE-IN SHALL BE PRE-CHLORINATED AND FLUSHED IN THE PRESENCE OF A DISTRICT INSPECTOR.
3. ABOVE-GROUND CONSTRUCTION WATER SERVICE SHALL BE SAFE-GUARDED WITH BARRICADES.
4. THE CONTRACTOR MAY CONNECT TO A DISTRICT FIRE HYDRANT INSTEAD OF A DISTRICT WATER MAIN AT THE SOLE DISCRETION OF THE INSPECTOR.



## 2" CONSTRUCTION WATER SERVICE

**CITRUS HEIGHTS WATER DISTRICT**

APPROVED BY: Robert A. Chubria DATE: 4/13/2009  
 CITRUS HEIGHTS WATER DISTRICT

DRAWN: 13 APR 2009
REVISED:
SCALE: N.T.S.
DESIGN: P.A.D.
CAD FILE: WS_221.DWG
PAGE: <span style="font-size: 1.5em; font-weight: bold;">WS_290</span>